

Reconstruction of South County Road 1110

Roadway Improvements to Serve Midland County					
		Quantity	Unit	Unit Price	Total
Base Bid					
Item	Description				
1	Preparation of R.O.W.	107	Sta.		
2	Sawcut Existing Asphalt (full depth)	321	L.F.		
3	Asphalt Excavation - 1 inch depth (average)	844	C.Y.		
4	Asphalt Haul Off	844	C.Y.		
5	Earthwork	18,374	C.Y.		
6	Haul Off	18,374	C.Y.		
7	Subgrade Preparation (Roadway)	53,001	S.Y.		
8	Prime Coat	12,685	Gal.		
9	Flexible Base (Roadway)	17,836	C.Y.		
10	HMA Pavement - 3" thickness - Type D	7,294	Ton		
11	Concrete Pavement at Intersections and Cul de Sac	3,940	S.Y.		
12	6" Concrete Commercial Driveways	50	S.Y.		
13	3" HMA on 8" Base Commercial Driveway	100	S.Y.		
14	8" Compacted Base Commercial Driveway	900	S.Y.		
15	8" Compacted Base Residential Driveway	110	S.Y.		
16	6" Concrete Residential Driveways	150	S.Y.		
17	3" HMA on 8" Base Residential Driveway	40	S.Y.		
18	Reinforced Concrete Box (RCB) - 5' x 2'	40	L.F.		
19	Safety End Treatments with 30° Wing Walls (1 - RCB 5'x2')(HW=3)(4:1)	2	Ea.		
20	Reflective Marking (Type 1) 4" Double Yellow Striped	62	Sta.		
21	Reflective Marking (Type 1) 4" Broken Yellow Striped	89	Sta.		
22	Reflective Marking (Type 1) 4" White Striped	107	Sta.		

23	Reflective Marking (Type 1) 8" Yellow Striped	89	LF		
24	18" Stop Bar Pavement Marking	100	L.F.		
25	Left Turn Arrow	1	Ea.		
26	Surface Preparation for Pavement Marking	107	Sta.		
27	IN SM RD SN SUP&AM TY10BWG(1) SA (P)	19	Ea.		
28	Aluminum Signs	138	S.F.		
29	Mailbox Relocations	6	Ea.		
30	Erosion Control	1	L.S.		
31	Traffic Control	1	L.S.		
32	Mobilization	1	L.S.		
TOTAL BASE BID FOR SCR 1110					
CONSTRUCTION START DATE FOR SCR 1110					
TOTAL CALENDAR DAYS FOR SCR 1110					

Contractor shall notify the Engineer of Record of any discrepancies in quantities prior to the commencement of construction.

* Quantities do not include factors for compaction and expansion.

** Rates used for calculation purposes only:

Prime Coat: 0.3 Gal/SY

HMA Pavement - 3" thickness - Type D: 115 lb/SY*in