

Construction of East County Road 120 & FM 715 Turn Lane Addition

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Revised Bid 8/1/2025					
Item	Description				
1	Preparation of R.O.W.	18	Sta.		
2	Sawcut Existing Pavement (full depth)	940	L.F.		
3	Earthwork	597	C.Y.		
4	Haul Off	597	C.Y.		
5	Subgrade Preparation (Roadway)	1,980	S.Y.		
6	Prime Coat	323	Gal.		
7	Flexible Base (Roadway)	264	C.Y.		
8	HMA Pavement - 3" thickness - Type D	186	Ton		
9	Concrete Pavement at Intersections and Cul de Sac	687	S.Y.		
10	Remove Concrete Curb & Gutter	80	L.F.		
11	Remove Existing Striping	18	Sta.		
12	Reflective Marking (Type 1) 4" Double Yellow Striped	11	Sta.		
13	Reflective Marking (Type 1) 4" White Striped	23	Sta.		
14	Reflective Marking (Type 1) 8" White Dotted	6	Sta.		
15	18" Stop Bar Pavement Marking	62	L.F.		
16	Left Turn Arrow	2	Ea.		
17	Thru Arrow	2	Ea.		
18	Surface Preparation for Pavement Marking	23	Sta.		
19	IN SM RD SN SUP&AM TY10BWG(1) SA (P)	4	Ea.		
20	Aluminum Signs	25	S.F.		
21	Erosion Control	1	L.S.		
21	Traffic Control	1	L.S.		
22	Mobilization	1	L.S.		
TOTAL REVISED BID FOR ECR 120 & FM 715 TURN LANE					
CONSTRUCTION START DATE FOR ECR 120 & FM 715 TURN LANE					
TOTAL CALENDAR DAYS FOR ECR 120 & FM 715 TURN LANE					

Contractor shall notify the Engineer of Record of any discrepancies in quantities prior to the commencement of construction.

* Quantities do not include factors for compaction and expansion.

** Rates used for calculation purposes only:

Prime Coat: 0.3 Gal/SY

HMA Pavement - 3" thickness - Type D: 115 lb/SY*in