



## RFP 25MCO655

### In response refer to RFP No. 25MCO655 Response to Questions September 5, 2025

Ladies/Gentlemen,

This document contains the following questions submitted by prospective bidders and responses to those questions.

1. Can AE-P be Used in lieu of MC-30?

**Yes.**

2. Will the county coordinate with the awarded contractor where the New proposed 34-wheel stops will be placed?

**Yes.**

3. What's the existing paving section?

**2" average depth.**

4. How much existing asphalt are we to remove?

**Remove all existing asphalt to the flex base.**

5. There are three utility trenches that go to the Tower next to the video visitation building are they well backfilled, what's the paving section? What's required?

**Price needs to include any prep work that may be needed.**

6. Are the bumper blocks around the tower to be removed and replaced with new ones?

**No.**

7. Is there any phasing to pave the parking lot? Is the "employee parking only" parking (cars) to be relocated front of the annex building?

**Plan on 3 phases to minimize business disruption.**

8. There are two water valves, are they to remain in place or lowered/raised to level new asphalt? What's required?

**Valves need to match finish grade of asphalt.**