



Request for Proposal, 19MCO557

In response refer to RFP No. 19MCO557 Addendum 2 and Response to Questions January 17, 2020

Gentlemen/Ladies:

Please note that there have been changes to the specifications made to the original request for proposal. These changes are provided on pages 2 and 3 of this addendum. This document also contains a follow up question submitted by prospective bidders and responses to those questions.

1. Can you clarify the signs? Proposal shows line item 25 with a quantity of 9 but when you look at and count the number of sign on the plans, there are 25?

There are 25 signs. A revised bid tab is being issued in this Addendum.

Reconstruction of South Fairgrounds Road

Roadway Improvements to Serve Midland County					
		Quantity	Unit	Unit Price	Total
Base Bid					
Item	Description				
1	Preparation of R.O.W. (60' ROW)	86	Sta.		
2	Relocate Mailboxes	1	L.S.		
3	Remove Concrete Curb or Curb and Gutter	183	L.F.		
4	Remove Concrete Pavement (full depth)	1,079	S.Y.		
5	Sawcut Existing Asphalt (full depth)	483	L.F.		
6	Asphalt Excavation - 1.5 inch depth (average)	1,464	C.Y.		
7	Asphalt Haul Off	1,464	C.Y.		
8	Earthwork	22,677	C.Y.		
9	Haul Off	22,677	C.Y.		
10	Subgrade Preparation	39,226	S.Y.		
11	Prime Coat	9,485	Gal.		
12	Flexible Base (Roadway and Driveways)	10,674	C.Y.		
13	HMA Pavement - 3" thickness - Type D	5,454	Ton		
14	Concrete Pavement at Intersections	1,810	S.Y.		
15	6" Concrete Driveways	928	S.Y.		
16	6" Concrete Curb and Gutter	180	L.F.		
17	Concrete Pads for Exist. Water Valves	6	Ea.		
18	Concrete Pads for Exist. Sanitary Sewer Manhole	1	Ea.		
19	60'x5' Pipeline Cap	11	Ea.		
20	Reflective Marking (Type 1) 4" Double Yellow Striped	85	Sta.		
21	Reflective Marking (Type 1) 4" Broken Yellow Striped	2	Sta.		

Reconstruction of South Fairgrounds Road

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Base Bid					
Item	Description				
22	Reflective Marking (Type 1) 4" White Striped	4	Sta.		
23	18" Stop Bar Pavement Marking	40	L.F.		
24	Surface Preparation for Pavement Marking	91	Sta.		
25	IN SM RD SN SUP&AM TY10BWG(1) SA (P)	25	Ea.		
26	Aluminum Signs	61	S.F.		
27	Erosion Control	1	LS		
28	Traffic Control	1	LS		
29	Mobilization	1	LS		
TOTAL BASE BID					
CONSTRUCTION START DATE					
TOTAL CALENDAR DAYS					