

Construction of South County Road 1232 Extension at Monahan's Draw

Roadway Improvements to Serve Midland County					
		Quantity	Unit	Unit Price	Total
Base Bid - Revised 04/20/2021					
Item	Description				
1	Preparation of R.O.W.	22	Sta.		
2	5 Strand Barb Wire Fence with H Braces	0	L.F.		
3	Earthwork*	9,786	C.Y.		
4	Import*	7,455	C.Y.		
5	Subgrade Preparation	8,800	S.Y.		
6	Prime Coat**	960	Gal.		
7	Flexible Base (Roadway and Driveways)	2,499	C.Y.		
8	HMA Pavement - 3" thickness - Type D **	552	Ton		
9	32'x100' Pitched Concrete Pavement Section	13	Ea.		
10	60'x5' Pipeline Cap	4	Ea.		
11	Reflective Marking (Type 1) 4" Double Yellow Striped	22	Sta.		
12	Reflective Marking (Type 1) 4" Solid White Striped	22	Sta.		
13	Surface Preparation for Pavement Marking	22	Sta.		
14	IN SM RD SN SUP&AM TY10BWG(1) SA (P)	4	Ea.		
15	Aluminum Signs	30	S.F.		
16	CONTECH BRIDGECORE SYSTEM	1	LS		
17	Headwall (PW) (CONTECH BRIDGECORE SYSTEM) (10'-6")	2	Ea.		
18	MTL W-BEAM GD FEN (STEEL POST)	500	L.F.		
19	RAIL (TY T66)	923	L.F.		
20	MTL THRIE-BEAM GD FEN (TIM POST)	4	Ea.		
21	50' Guardrail Terminal MSKT-MASH-TL-3	2	Ea.		

Construction of South County Road 1232 Extension at Monahan's Draw

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Base Bid - Revised 04/20/2021					
Item	Description				
22	10' Downstream Anchor Terminal (DAT)	2	Ea.		
23	Erosion Control	1	LS		
24	Traffic Control	1	LS		
25	Mobilization	1	LS		
TOTAL BASE BID					
CONSTRUCTION START DATE					
TOTAL CALENDAR DAYS					

Contractor shall notify the Engineer of Record of any discrepancies in quantities prior to the commencement of construction.

* Quantities do not include factors for compaction and expansion.

** Rates used for calculation purposes only:

Prime Coat: 0.3 Gal/SY

HMA Pavement - 3" thickness - Type D: 115 lb/SY*in

Construction of South County Road 1232 Extension at Monahan's Draw

Roadway Improvements to Serve Midland County					
		Quantity	Unit	Unit Price	Total
Alternate Bid					
Item	Description				
19-ALT	RAIL (TY T223)	923	L.F.		
TOTAL ALTERNATE BID					