

Cholla Road and CR 1250					
Item No.	Description	Quantity	Unit	Unit Price	Amount
1	Preparation of R.O.W.	97.23	STA		\$
2	Subgrade Preparation (Dens Cont)	37,385	SY		\$
3	Remove 8" HMAC + 10" Flex Base	992	SY		\$
4	Prime Coat (MC-30)	8,400	GAL		\$
5	Flex Base (8")(Ty A)(Gr 1-2)(Complete in Place) (Dens Cont)	1,715	SY		\$
6	Flex Base (11")(Ty A)(Gr 1-2)(Complete in Place) (Dens Cont)	35,941	SY		\$
7	HMA Pavement (3" TYPE C)	5,502	TON		\$
8	Concrete Pavement (6")(complete in place)	271	CY		\$
9	Concrete Curb and Gutter (Ty A)	253	LF		\$
10	CURB RAMPS (TY 8)	2	EA		\$
11	CURB RAMPS (TY 10)	1	EA		\$
12	REFL PAV MRK PRE-FAB THERMO (W) 24" (SLD)	61	LF		\$
13	REFL PAV MRK TY II (W) 4" (SLD)	200	LF		\$
14	REFL PAV MRK TY II (Y) 4" (SLD)	19,340	LF		\$
15	REFL PAV MRK PRE-FAB THERMO (W) (ARROW)	2	EA		\$
16	SM RD SN SUP&AM TY 10BWG(1) SA(P)	8	EA		\$
17	Aluminum Signs	80	SF		\$
18	Adjust Water Valve Covers	4	EA		\$
19	Barbed Wired Fence (4 strand with tee posts)	8,580	LF		\$
20	Rock Riprap (8" Depth) (Stone size between 4" and 8") (Diag 4, Sheet 35)	214	SY		\$

Cholla Road and CR 1250					
Item No.	Description	Quantity	Unit	Unit Price	Amount
21	Site Stabilization (drill seeding and watering)	1	LS		\$
22	Erosion Control	1	LS		\$
23	Traffic Control	1	LS		\$
24	Mobilization	1	LS		\$
TOTAL BASE BID					\$
CONSTRUCTION START DATE					
TOTAL CALENDAR DAYS					