

SPECIFICATIONS AND BID ITEMS

FOR

**Construction of South County Road 1232 Driveway
At State Highway 158
and Associated State Highway 158 Improvements**

COUNTY JUDGE

Terry Johnson

COUNTY COMMISSIONERS

Scott Ramsey – Precinct 1

Robin Donnelly – Precinct 2

Luis D. Sanchez – Precinct 3

Randy Prude – Precinct 4

PREPARED BY



Dunaway No. B001484.012

June 2021

TABLE OF CONTENTS

PART A – Standard Specifications

PART B – Guide Schedule of Sampling and Testing – June 2019**

PART C – Bid Quantities

**Laboratory and Field Testing to be provided by the County and is not considered a part of this bid.

PART A

STANDARD SPECIFICATIONS

Contractor shall follow specifications adopted by the Texas Department of Transportation, November 14, 2014 and any additional Special Specifications as stated in the plans.

PART B

GUIDE SCHEDULE OF SAMPLING AND TESTING

GUIDE SCHEDULE OF SAMPLING & TESTING FOR DESIGN BID-BUILD (DBB) PROJECTS - (DBB Guide Schedule)

JUNE 28, 2019



Using the Guide Schedule

Research of sampling and testing rates, listed for project tests in the following Guide Schedule, show that the Department's and the Contractor's risk of either rejecting "good" material or accepting "bad" material range from 20% to 40%.

To reduce this risk, we recommend that the sampling rate be increased during initial production. A four-fold increase in testing frequency will generally reduce risk to approximately 5%. The intent of increasing testing, at the start of production, is to insure the Contractor's processes are in control and to establish acceptability requirements early.

There is a need to increase the frequency of testing for high-variability materials and when testing results do not meet specifications. The Engineer may require the Contractor to reimburse the Department for costs resulting from failing test results, in accordance with the specifications.

Materials incorporated in TxDOT projects are subjected to various quality assurance procedures such as testing (as outlined in this document), certification, quality monitoring, approved lists, etc. The Engineer and testing staff should familiarize themselves with materials to be used before work begins by reviewing the specifications and this document. Discuss material testing requirements with the Contractor.

Other testing required by the specifications, but not shown in the DBB Guide Schedule, should be performed at a frequency necessary to provide adequate confidence that materials meet specifications.

NOTE—The TxDOT District Area Engineer or Director of Construction must submit a "Materials Certification Letter" at final acceptance of the project. The intent of this letter is to ensure that the quality of all materials incorporated into the project is in conformance with the plans and specifications, thus ensuring a service life equivalent to the design life. Any material represented by an acceptance test, that does not meet the criteria contained in the plans and specifications, is considered an exception. Exceptions must be listed in the materials certification letter. For projects with federal oversight, submit the materials certification letter (See Appendix D of DBB QAP) to the FHWA division administrator, with a copy to **the Materials and Tests Division (MTD)**. For non-federal oversight projects, submit the material certification letter (Appendix E of DBB QAP) to the TxDOT District Engineer, with a copy to **MTD**. Refer to section 4.1 of the "Quality Assurance Program for Design-Bid-Build Projects" (DBB QAP).

Assuring the quality of the product and proper incorporation of materials into the project begins with proper sampling practices. Sampling, testing, and construction inspection must be performed collaboratively to assure the specific attributes of the finished product reflect quality workmanship. Sampling guidance for hot-mix asphalt is contained in Tex-225-F, "Random Selection of Bituminous Mixture Samples," and the respective specification for that material. All remaining materials are covered by method and materials specifications, to which the following applies.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows:

- Soils/flexible base: Vary sampling between stockpiling operations, completed stockpile, windrow, and project site. Vary the time of day sampling is performed.
- Aggregates: Sample aggregates nearest the point of incorporation into the work. Vary sampling between stockpiling operations, completed stockpile, belt sampling, and if deemed necessary, railroad cars/trucks. Vary the time of day sampling is performed.
- Concrete (structural and miscellaneous): Always sample as near as practicable to the point of placement. For strength testing, vary the time of day or the number of truck from which the concrete is sampled. Tests for slump, air, and temperature should be done often to ensure the consistent control of the concrete production (not applicable to miscellaneous concrete).

This Guide Schedule is applicable to all contracts associated with the 2014 Standard Specifications.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	REMARKS
EMBANKMENT (CUTS & FILLS)	Liquid Limit (A)	Tex-104-E	During stockpiling operations, from completed stockpile, or project site (B)	Materials with PI ≤ 15: 10,000 CY	For Type A embankment or when required by the plans. This test may be waived for embankment cuts as directed by the Engineer . Determine a new liquid limit and plasticity index for each different material or notable change in material. Sample in accordance with Tex-100-E. When shown on plans. This test may be waived for embankment cuts, as directed by the Engineer. Sample in accordance with Tex-100-E. Not required for ordinary compaction. Determine a new optimum moisture and maximum density for each different material or notable change in material. Sample in accordance with Tex-100-E. Not required for ordinary compaction. Determine a new optimum moisture and maximum density according to Tex-114-E for each different material or notable change in material. Correct the moisture contents measured by nuclear density gauge in Tex-115-E with the moisture contents determined in accordance with Tex-103-E, as necessary for control, for each different material or notable change in material and adjust the density accordingly. Materials such as RAP, gypsum, lime, cement, and iron ore tend to bias the counts for nuclear density gauges.
	Plasticity Index (A)	Tex-106-E		Materials with PI > 15: 5,000 CY	
	Gradation	Tex-110-E		Each 10,000 CY	
	Moisture/Density	Tex-114-E		As directed by the Engineer	
	In-place Density (A)	Tex-115-E	As directed by the Engineer	Fill: each 5,000 CY min. 1 per lift.	
Cut: each 6,000 LF					
RETAINING WALL (NON-SELECT BACKFILL)	As shown above for Embankment (Cuts and Fills)		As shown above for Embankment (Cuts and Fills)	As shown above for Embankment (Cuts and Fills)	Sample in accordance with Tex-100-E.
RETAINING WALL (SELECT BACKFILL)	Plasticity Index (A)	Tex-106-E	During stockpiling operations, from completed stockpile, or project site (B)	Each 5,000 CY	Required only for Type CS backfill . Test the fraction of material finer than the No. 200 sieve. Sample in accordance with Tex-400-E.
	Gradation	Tex-110-E	During stockpiling operations, from completed stockpile, or project site (B)	Each 5,000 CY	Required only for Drainage Aggregate. Sample in accordance with Tex-400-A.
		Tex-401-A			Required only for Select Backfill. Sample in accordance with Tex-400-A.
Resistivity (A)	Tex-129-E	During stockpiling operations, from completed stockpile, or project site (B)	Each 5,000 CY	For material with resistivity between 1,500 and 3,000 ohm-cm, determine chloride and sulfate content, as specified in Item 423. Sample in accordance with Tex-400-A.	

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	REMARKS
RETAINING WALL (SELECT BACKFILL) (continued)	pH (A)	Tex-128-E	During stockpiling operations, from completed stockpile, or project site (B)	Each 5,000 CY	Sample in accordance with Tex-400-A.
	Magnesium Soundness	Tex-411-A	During stockpiling operations, or from completed stockpile	1 per source, per project	Test when backfill sources appear to contain particles such as shale, caliche, or other soft, poor-durability particles. Sample in accordance with Tex-400-A.
	Micro-Deval	Tex-461-A	During stockpiling operations, or from completed stockpile	1 per source, per project	May be used as an alternate to the magnesium soundness only when the % loss from the micro-deval is not greater than 20%. When the % loss from the micro-deval is greater than 20%, the magnesium soundness governs aggregate verification. Sample in accordance with Tex-400-A.
	In-place Density (A)	Tex-115-E	As directed by the Engineer.	1 per backfill lift, per wall	Not required for rock backfill. For walls greater than 500 ft. in length, perform one test per lift for every 500 ft. in length. (F) Correct the moisture contents measured by nuclear density gauge in Tex-115-E with the moisture contents determined in accordance with Tex-103-E for each different material or notable change in material and adjust the density accordingly.
UNTREATED BASE COURSES	Liquid Limit (A)	Tex-104-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	Sample in accordance with Tex-400-A.
	Plasticity Index (A)	Tex-106-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	
	Gradation (A)	Tex-110-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	Sample in accordance with Tex-400-A.
	Moisture/Density	Tex-113-E	From completed stockpile at the source (E)	Each 20,000 CY	Not required for ordinary compaction. Sample in accordance with Tex-400-A.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES

			PROJECT TESTS			
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	REMARKS	
UNTREATED BASE COURSES (Continued)	Wet Ball Mill (A)	Tex-116-E	From completed stockpile at the source (E)	Each 20,000 CY	Required for Grades 1–2 and 5, and as shown on the plans for Grade 4. Sample in accordance with Tex-400-A.	
	Strength (A)	Tex-117-E	From completed stockpile at the source (E)	Each 20,000 CY	Required for Grades 1–2 and 5, and as shown on the plans for Grade 4. When base material is from a source where the District has a record of satisfactory triaxial results, the frequency of testing may be reduced to one per 30,000 CY. If any one test falls below the minimum value required, the frequency of testing will return to the original frequency of 20,000 CY. Sample in accordance with Tex-400-A.	
	In-place Density (A)	Tex-115-E	As directed by the Engineer	Each 3,000 CY, min. 1 per lift	Correct the moisture contents measured by nuclear density gauge in Tex-115-E with the moisture contents determined in accordance with Tex-103-E, as necessary for control, for each different material or notable change in material and adjust the density accordingly. Materials such as RAP, gypsum, lime, cement, and iron ore tend to bias the counts for nuclear density gauges.	
	Thickness (A)	Tex-140-E	As directed by the Engineer	Each 3,000 CY	Not required where survey grade control documents are compliant.	
	Ride Quality (A)	Tex-1001-S Surface Test, Type B	Final riding surface of travel lanes		This applies to the final travel lanes that receive a 1- or 2-course surface treatment for the final surface, unless otherwise shown on the plans.	
TREATED SUBGRADE AND BASE COURSES	SUBGRADE BEFORE TREATMENT	Organic Content	Tex-148-E	As directed by the Engineer	1 per project, per source or as directed by the Engineer	Required for existing subgrade material and material imported from a borrow source. Soil survey and geologic maps may be used to determine sampling locations. Sample in accordance with Tex-100-E.
	SUBGRADE BEFORE TREATMENT	Sulfate Content	Tex-145-E	As directed by the Engineer	1 per 500 feet or 5,000 CY	Required for existing subgrade material and material imported from a borrow source. Soil survey and geologic maps may be used to determine sampling locations. Sample in accordance with Tex-100-E.
	NEW BASE MATERIAL	Liquid Limit (A)	Tex-104-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	When central mix site or plant is used, windrow sampling may be waived. Sample in accordance with Tex-400-A.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES

			PROJECT TESTS			
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	REMARKS	
TREATED SUBGRADE AND BASE COURSES (Continued)	NEW BASE MATERIAL (Continued)	Plasticity Index (A)	Tex-106-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	
		Gradation (A)	Tex-110-E	During stockpiling operations, from completed stockpile, or windrow (B)	Each 5,000 CY	Sample in accordance with Tex-400-A.
		Wet Ball Mill (A)	Tex-116-E	From completed stockpile at the source (E)	Each 20,000 CY	Required for Grades 1–2 and 5, and as shown on the plans for Grade 4. Sample in accordance with Tex-400-A.
		Strength (A)	Tex-117-E	From completed stockpile at the source (E)	Each 20,000 CY	Required for Grades 1–2 and 5, and as shown on the plans for Grade 4. When base material is from a source where the District has a record of satisfactory triaxial results, the frequency of testing may be reduced to one per 30,000 CY. If any one test falls below the minimum value required, the frequency of testing will return to the original frequency of 20,000 CY.
	LIME	Compliance with DMS-6350	Tex-600-J	During delivery to project	Commercial Lime Slurry: each 200 tons of lime Carbide Lime Slurry: each 100 tons of lime	Sample in accordance with Tex-600-J. Verify the source is listed on the current Material Producer List for Lime. Only materials appearing on the Material Producer List will be accepted. Sample frequency for Carbide Lime Slurry may be increased as directed by the Engineer. For Hydrated Lime and Quick Lime, project testing is not required but it is encouraged to sample and test the material at a rate of 1 per project as a best practice.
	CEMENT	Compliance with DMS-4600		Railroad car, truck, or cement bins		Verify the source is listed on the current Material Producer List for Cement. If not, sample and test in accordance with DMS-4600. (C)
	FLY ASH MATERIAL	Compliance with DMS-4615		Project samples at location directed by the Engineer		Verify the source is listed on the current Material Producer List for Fly Ash. Only materials from MTD approved sources appearing on the Material Producer List for Fly Ash will be accepted. Project testing is not required but it is encouraged to sample and test the material at a rate of 1 per project as a best practice. (C)

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES

MATERIAL OR PRODUCT		TEST FOR	TEST NUMBER	PROJECT TESTS		REMARKS
				LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	
TREATED SUBGRADE AND BASE COURSES (Continued)	COMPLETE MIXTURE	Pulverization Gradation	Tex-101-E, Part III	Roadway, after pulverization and mixing	As necessary for control	At the beginning of the project, one test must be made for each 4,500 CY or 6,000 tons until the Engineer is satisfied that acceptable pulverization results are being obtained. Sample in accordance with Tex-100-E.
		Moisture/Density Curve and Strength	Tex-120-E, Part II, or Tex-121-E, Part II	From roadway windrow after treatment (E)	Each 20,000 CY	Not required for ordinary compaction. Determine a new moisture/density curve for each different or notable change in material. Perform Tex-120-E, Part II, for Cement Treated Material, and Tex-121-E, Part II, for Lime, Lime-Fly Ash, or Fly Ash Treated Material. If Tex-120-E, Part I, Tex-121-E, Part I, or Tex-127-E is performed before the project, this test may be waived. Sample in accordance with Tex-100-E.
		Moisture/Density Curve and Strength	Tex-120-E, Part I, Tex-121-E, Part I, or Tex-127-E	From roadway before treatment	As necessary for control	Perform Tex-120-E, Part I, on cement treated material, and Tex-121-E, Part I, for lime-fly ash or fly ash treated material. Verifies the field strength by comparing results from the mix design. Performed at the direction of the Engineer and when notable change in material, as described above for Part II of the test procedures. Sample in accordance with Tex-100-E.
		In-place Density (A)	Tex-115-E	As directed by the Engineer	Each 3,000 CY, min 1 per lift	Determine the appropriate moisture/density curve for each different material or notable change in material. Correct the moisture contents measured by nuclear density gauge in Tex-115-E with the moisture contents determined in accordance with Tex-103-E, as necessary for control, for each different material or notable change in material and adjust the density accordingly. Stabilizers and materials such as RAP, gypsum, and iron ore tend to bias the counts for nuclear density gauges.
		Thickness (A)	Tex-140-E	As directed by the Engineer	Each 3,000 CY	Not required where survey grade control documents are used for compliance.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE I – EMBANKMENTS, SUBGRADES, BACKFILL, AND BASE COURSES					
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	PROJECT TESTS		REMARKS
			LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (F)	
RECLAIMED ASPHALT PAVEMENT (RAP), CRUSHED CONCRETE, and RECYCLED MATERIALS	Sulfate Content	Tex-145-E	During stockpiling operations, from completed stockpile, or windrow	Each 5,000 CY	Required only for contractor furnished recycled material, including crushed concrete. Not required for RAP. Sample in accordance with Tex-400-A.
	Deleterious Material	Tex-413-A		Each 5,000 CY	Required only for contractor furnished recycled material, including crushed concrete. Sample in accordance with Tex-400-A.
	Decantation	Tex-406-A	During stockpiling operations, from completed stockpile, or windrow	Each 5,000 CY	Required only for contractor furnished RAP. Sample in accordance with Tex-400-A.

TABLE I – FOOTNOTES	
A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager (SM), in the remarks field, and on the end of the Project Materials Certification Letter.
B	Engineer will select any of these locations or any combinations thereof with the provision that the initial sample will be obtained from the completed stockpile at the source and at least one out of ten consecutive samples will be taken at the project site (from the windrow for treated and untreated bases and embankments when possible).
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows: <ul style="list-style-type: none"> • Soils/Flexible Base: For gradation, liquid limit, and plastic limit, vary sampling between stockpiling operations, completed stockpile, windrow, and project site. Vary the time of day sampling is performed. • Aggregates: Sample aggregates nearest the point of incorporation into the work. Vary sampling between stockpiling operations, completed stockpile, belt sampling, and if deemed necessary, railroad cars/trucks. Vary the time of day sampling is performed.
E	The Engineer will sample from the completed stockpile at the source and test before placement.
F	Each test performed that is based on a quantity of material is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IA – ASPHALT TREATED BASE (Plant Mix)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (C)	FREQUENCY OF SAMPLING (D)	REMARKS
AGGREGATE	Liquid Limit (A)	Tex-104-E	During stockpiling operations, from completed stockpile, or before mixing	Each 5,000 CY	Sample in accordance with Tex-400-A.
	Plasticity Index (A)	Tex-106-E	During stockpiling operations, from completed stockpile, or before mixing	Each 5,000 CY	
	Wet Ball Mill (A)	Tex-116-E	During stockpiling operations, from completed stockpile, or before mixing	1 per project, per source	Sample in accordance with Tex-400-A. (B)
LIME	Compliance with DMS-6350		During delivery to the project	Hydrated Lime: 1 per project Commercial Lime Slurry: each 200 tons of lime (D) Carbide Lime Slurry: each 100 tons of lime (D) Quick Lime: 1 per project	On projects requiring less than 50 tons, material from MTD approved sources may be accepted on the basis of Producer's Certification without sampling.
RECLAIMED ASPHALT PAVEMENT (RAP), and RECYCLED AGGREGATE	Decantation	Tex-406-A, Part I	During stockpiling operations, from completed stockpile, or before mixing	Each 10,000 CY	Sample in accordance with Tex-400-A.
RECYCLED ASPHALT SHINGLES (RAS)	Decantation	Tex-217-F, Part III	During stockpiling operations, from completed stockpile, or before mixing	Each 10,000 CY	Sample in accordance with Tex-400-A.
ASPHALT BINDER	Compliance with Item 300		Sampling port nearest the storage tank	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample binder in accordance with Tex-500-C, Part II. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SiteManager (SM) Assistant. The Engineer must associate one QM sample per project in SM.

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IA – ASPHALT TREATED BASE (Plant Mix)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (C)	FREQUENCY OF SAMPLING (D)	REMARKS
TACK COAT	Compliance with Item 300		Distributor	1 per project, per grade, per source	<p>Test a minimum of one sample taken from the project. Sample tack coat in accordance with Tex-500-C, Part III.</p> <p>Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant.</p> <p>The Engineer must associate one QM sample per project in SM.</p>
COMPLETE MIXTURE	Gradation (A)	Tex-200-F, Part I	Plant Mix (C)	20,000 CY (25,000 tons)	<p>Sample in accordance with Tex-222-F.</p> <p>Determine the gradation of the aggregate from the complete mixture tested in accordance with Tex-236-F.</p>
	Laboratory Density (A)	Tex-126-E	Plant Mix (C)	20,000 CY (25,000 tons)	Sample in accordance with Tex-222-F.
	Percent Asphalt (A)	Tex-236-F	Plant Mix (C)	Each 1,500 CY (2,000 tons) or days production	Determine an asphalt content correction factor for ignition oven at a minimum of one per project. Sample in accordance with Tex-222-F.
	Indirect Tensile Strength – Dry	Tex-226-F	Plant Mix	1 per project, per design	Sample in accordance with Tex-222-F.
	Moisture Susceptibility	Tex-530-C	As directed by the Engineer	1 per project, per design	This test may be waived, when shown on the plans. Sample in accordance with Tex-222-F.
ROADWAY	In-Place Air Voids (A)	Tex-207-F	Roadway cores, as directed by the Engineer (C, D)	Each 3,000 CY, min 1 per lift	Not required for ordinary compaction or when air void requirements are waived. Sample in accordance with Tex-222-F.
	Ride Quality	Tex-1001-S Surface Test, Type A	On Finished Surface		Unless otherwise shown on the plans.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IA – FOOTNOTES	
A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager (SM), in the remarks field, and on the end of the Project Materials Certification Letter.
B	Engineer will select any of these locations or any combinations thereof with the provision that at least one out of ten consecutive samples will be taken at the project site (from the windrow for treated and untreated bases and embankments when possible).
C	For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows: <ul style="list-style-type: none">• Soils/Flexible Base: Vary sampling between stockpiling operations, completed stockpile, windrow, and project site. Vary the time of day sampling is performed.• Aggregates: Sample aggregates nearest the point of incorporation into the work. Vary sampling between stockpiling operations, completed stockpile, belt sampling, and if deemed necessary, railroad cars/trucks. Vary the time of day sampling is performed.
D	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE II – SEAL COAT					
			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (C)	FREQUENCY OF SAMPLING (D)	REMARKS
AGGREGATE	Gradation (A)	Tex-200-F, Part I	Stockpile (At source or at point of delivery)	Each 1,000 CY	Rate may be reduced to each 2,000 CY if the Engineer approves a contractor quality control plan. Sample in accordance with Tex-221-F.
	L. A. Abrasion (A)	Tex-410-A	Stockpile	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample and test at 1 per 20,000 CY before use. Sample in accordance with Tex-221-F. (B)
	Magnesium Soundness (A)	Tex-411-A	Stockpile	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample and test at 1 per 20,000 CY before use. Sample in accordance with Tex-221-F. (B)
	Surface Aggregate Classification (A)	Tex-612-J, Tex-411-A	Stockpile	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample and test at 1 per 20,000 CY before use. Sample in accordance with Tex-221-F. (B)
	Pressure Slake (A)	Tex-431-A	Stockpile	1 per 20,000 CY	Same as above. Required only for lightweight aggregate. Sample in accordance with Tex-221-F.
	Freeze Thaw (A)	Tex-432-A	Stockpile	1 per 20,000 CY	Same as above. Required only for lightweight aggregate. Sample in accordance with Tex-221-F.
	Unit Weight	Tex-404-A	Stockpile	1 per 20,000 CY	Same as above. Required only for lightweight aggregate. Sample in accordance with Tex-221-F.
	24 hr. Water Absorption (A)	Tex-433-A	Stockpile	1 per 20,000 CY	Same as above. Required only for lightweight aggregate. Sample in accordance with Tex-221-F.
	Crushed Face Count	Tex-460-A, Part I	Stockpile	1 per 20,000 CY	Only required for crushed gravel. Sample in accordance with Tex-221-F.
	Deleterious Material (A)	Tex-217-F, Part I	Stockpile	1 per 10,000 CY	Not required for lightweight aggregate. Sample in accordance with Tex-221-F.
	Decantation (A)	Tex-406-A	Stockpile	1 per 10,000 CY	Sample in accordance with Tex-221-F.
Flakiness Index	Tex-224-F	Stockpile	Frequency as directed by the Engineer	Sample in accordance with Tex-221-F.	

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE II – SEAL COAT					
			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (C)	FREQUENCY OF SAMPLING (D)	REMARKS
AGGREGATE (Continued)	Micro Deval	Tex-461-A	Stockpile	1 per project or as necessary for control	Compare result to published value listed on the current Material Producer List for BRSQC . Submit sample to MTD for Soundness and L.A. Abrasion testing when results differ by more than 3% points, unless otherwise directed by the Engineer . Sample in accordance with Tex-221-F.
	White Rock Count	Tex-220-F	Stockpile		Required only for Limestone Rock Asphalt. Not required when MTD provides inspection at the plant. Sample in accordance with Tex-221-F.
	Naturally Impregnated Bitumen Content	Tex-236-F	Stockpile		Required only for Limestone Rock Asphalt. Not required when MTD provides inspection at the plant. Sample in accordance with Tex-221-F.
PRECOATED AGGREGATE	Asphalt Content	Tex-210-F	Stockpile	Frequency as directed by the Engineer when a target value is specified	Sample in accordance with Tex-221-F.
ASPHALT BINDER	Compliance with Item 300		Distributor	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample asphalt binder in accordance with Tex-500-C, Part III. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant. The Engineer must associate one QM sample per project in SM.

TABLE II – FOOTNOTES	
A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
C	For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows: <ul style="list-style-type: none"> Aggregates: Sample aggregates nearest the point of incorporation into the work. Vary sampling between stockpiling operations, completed stockpile, belt sampling, and if deemed necessary, railroad cars/trucks. Vary the time of day sampling is performed.
D	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE III – HYDRAULIC CEMENT CONCRETE – STRUCTURAL (Classes: C, F, H, S, CO, K, LMC, or SS)

			PROJECT TESTS			
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (E)	REMARKS	
MINERAL AGGREGATE	COARSE AGGREGATE	Decantation (B)	Tex-406-A	From stockpile at concrete plant	Each 20,000 CY of concrete (each source)	Sample in accordance with Tex-400-A.
		Sieve Analysis (A) (B)	Tex-401-A		Each 1,000 CY of concrete (each source)	Test combined aggregate when used. Sample in accordance with Tex-400-A.
		Deleterious Materials (B)	Tex-413-A		1 per project or as necessary for control	Sample in accordance with Tex-400-A.
		Los Angeles Abrasion (A) (B)	Tex-410-A		One, each source	Verify the value of the source, as listed on the current Material Producer list for CRSQC , meets the project specifications. If not, sample and submit to MTD for testing before use in accordance with Tex-499-A. Sample in accordance with Tex-400-A. (C)
		Magnesium Soundness (A) (B)	Tex-411-A		One, each source	Verify the value of the source, as listed on the current CRSQC , meets the project specifications. (C)
	FINE AGGREGATE	Sand Equivalent (B)	Tex-203-F	From stockpile at concrete plant	1 per project or as necessary for control	Test combined aggregate when used. Sample in accordance with Tex-400-A.
		Organic Impurities (B)	Tex-408-A		1 per project, per source	Sample in accordance with Tex-400-A.
		Sieve Analysis (A) (B)	Tex-401-A		Each 1,000 CY of concrete (each source)	Sample in accordance with Tex-400-A.
		Fineness Modulus (B)	Tex-402-A		1 per project or as necessary for control	Test combined aggregate when used. Test to confirm material variability when strength values are in question. Sample in accordance with Tex-400-A.
		Deleterious Material (B)	Tex-413-A		1 per project or as necessary for control	Test to confirm material variability when strength values are in question. Sample in accordance with Tex-400-A.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE III – HYDRAULIC CEMENT CONCRETE – STRUCTURAL (Classes: C, F, H, S, CO, K, LMC, or SS)						
			PROJECT TESTS			
MATERIAL OR PRODUCT		TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (E)	REMARKS
MINERAL AGGREGATE (Continued)	FINE AGGREGATE (Continued)	Acid Insoluble Residue (A) (B)	Tex-612-J		Two, each source	Only for concrete subject to direct traffic. Verify the value of the source, as listed on the current CRSQC , meets the project specifications. If not, sample and submit to MTD for testing before use in accordance with Tex-499-A. Sample in accordance with Tex-400-A. (C)
SILICA FUME		Compliance with DMS-4630 (A)		Railroad car, truck, bags or silos	1 per project, per class of concrete (For each type and brand)	Provide MTD with one 4 x 8 concrete sample for silica fume dispersion verification. Verify the source is listed on the Material Producer List for Silica Fume. Sample in accordance with Tex-300-D.
METAKAOLIN		Compliance with DMS-4635 (A)		Railroad car, truck or silos	1 per project, per class of concrete (For each type and brand)	Sample in accordance with Tex-300-D.
MIX DESIGN		Compliance with Standard Specification Item 421.4.A		At source (if not approved)	Min. 1 design per class, per source	Verify if cement, fly ash, slag cement, and chemical admixture sources are listed on the Material Producer Lists. If not, sample and submit to MTD for testing. Water testing is contracted by the concrete supplier (commercial lab report to be reviewed by TxDOT). Sample in accordance with Tex-300-D for cement and in accordance with Tex-733-I for fly ash.
JOINT MATERIAL		Compliance with DMS-6300				Verify the source is listed on the Material Producer List for Joint Sealers . If not, sample and test before use in accordance with DMS-6310. (C) Sample in accordance with Tex-500-C.
CURING COMPOUND		Compliance with DMS-4650		Sampled at jobsite; tested by MTD . See remarks.	When requested by MTD	Only products listed on the Material Producer List for Concrete Curing Compounds will be allowed. When sample is requested by MTD , sample in accordance with Tex-718-I. Ensure container has been agitated and mixed before sampling. (C)
EVAPORATION RETARDANTS		Compliance with DMS-4650				Only products listed on the Material Producer list for Evaporation Retardants will be allowed. (C)
REINFORCING STEEL		Compliance with the Std. Specifications & Spec. Provisions	As Specified			Only materials from MTD approved sources listed on the Material Producer Lists for Reinforcing Steel Mills and Seven Wire Steel Strand will be allowed. (C)

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE III – HYDRAULIC CEMENT CONCRETE – STRUCTURAL (Classes: C, F, H, S, CO, K, LMC, or SS)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (E)	REMARKS
MECHANICAL COUPLERS	Compliance with DMS-4510	Tex-743-I	Sampled at jobsite; Tested by MTD	3 couplers per lot (500 couplers) for each type, model, bar size, and grade	Only materials from MTD approved sources listed on the Material Producer List for Mechanical Couplers will be allowed. (C)
LATEX	Compliance with DMS-4640 for concrete chemical admixtures				Verify the Latex is listed on the Material Producer List for Chemical Admixtures.
EPOXY	Compliance with DMS-6100, unless otherwise specified		Sampled at jobsite if not pre-approved by MTD .	1 per batch or shipment	Verify the source is listed on the Material Producer List for Epoxies and Adhesives . If not, sample and test before use in accordance with DMS-6100. Sample in accordance with Tex-734-I. (C)
CONCRETE	Compressive Strength (A)	Tex-418-A	At point of concrete placement	4 cylinders for each 60 CY per class, per day (For bridge railing and traffic railing, testing may be reduced to 4 cylinders per 180 CY per class regardless of days)	Sampling must be in accordance with Tex-407-A. Making additional cylinders for 56 day testing should be considered when slow strength gain mixtures are being used, or when the approved mix design has a history of failing to meet design strength at 28 days. Test two cylinders at 7 days, and if the average value is below the design strength, as defined in Item 421, Table 8, test the remaining 2 cylinders at 28 days, or 56 days if additional cylinder were not made. If the average value of the 2 cylinders tested at 7 days meets the minimum design strength, listed in Item 421, Table 8, the remaining cylinders are not required to be tested. If the average value of the 7 and 28 day cylinders are below the design strengths, and 56 day cylinders were made, test the remaining set at 56 days.
	Slump	Tex-415-A		1 test, per 4 strength specimens	Sample in accordance with Tex-407-A. Perform slump and temperature tests on the same load from which strength test specimens are made. Perform entrained air test only when entrained air concrete is specified on the plans. Check temperature of every load for bridge slabs and mass concrete placements.
	Entrained Air (A)	Tex-416-A or Tex-414-A			Contractor's required testing will be in accordance with specification requirements for the appropriate specification Item #.
	Temperature of Concrete (A)	Tex-422-A			

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE III – HYDRAULIC CEMENT CONCRETE – STRUCTURAL (Classes: C, F, H, S, CO, K, LMC, or SS)					
			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (D)	FREQUENCY OF SAMPLING (E)	REMARKS
CONCRETE (Continued)	Bridge Deck or Culvert Top Slab Thickness and Depth of Reinforcement	Tex-423-A, Part II	During dry run and during concrete placement (Bridge decks and direct traffic culverts)	1 per span	Min 6–Max 18 locations per span.

TABLE III – FOOTNOTES	
A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	These Project Tests may be used for one or more projects being furnished concrete from the same plant during the same period.
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows: <ul style="list-style-type: none"> • Aggregates: Sample aggregates nearest the point of incorporation into the work. Vary sampling between stockpiling operations, completed stockpile, and if deemed necessary, railroad cars/trucks. Vary the time of day sampling is performed. • Concrete (structural): Always sample as near as practicable to the point of placement. For strength testing, vary the time of day or the number of truck from which the concrete is sampled. Test often for slump, air, and temperature to ensure the consistent control of the concrete production.
E	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IV – HYDRAULIC CEMENT CONCRETE – NON-STRUCTURAL CONCRETE (Classes: A, B, or E)					
			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING (B)	FREQUENCY OF SAMPLING (C)	REMARKS
CONCRETE	Compressive Strength (A)	Tex-418-A	At point of concrete placement	2 cylinders per 180 CY, per class	Sampling must be in accordance with Tex-407-A. Strength will be determined by 7-day specimens.
MIX DESIGN	Compliance with the Standard Specification		At source if not approved	Min. 1 design per class, per source	Verify if cement, fly ash, slag cement, and chemical admixture sources are listed on the Material Producer Lists. If not, sample and submit to MTD for testing. Sample in accordance with Tex-300-D for cement and in accordance with Tex-733-I for fly ash. Water testing is contracted by the concrete supplier (commercial lab report to be reviewed by TxDOT).
SILICA FUME	Compliance with DMS-4630		Railroad car, truck, bags, or silos	1 test per project, per class (for each type and brand)	Sample in accordance with Tex-300-D. Provide MTD with one 4 x 8 concrete sample for silica fume dispersion verification. Verify the source is listed on the Material Producer List for Silica Fume.
METAKAOLIN	Compliance with DMS-4635		Railroad car, truck, or silos	1 test per project, per class (for each type and brand)	Sample in accordance with Tex-300-D.

TABLE IV – FOOTNOTES	
A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	For acceptance testing, especially that which directly determines payment for the Contractor, sampling personnel should provide randomness in sampling by avoiding patterned sampling routines. Examples of such sampling practices are as follows: <ul style="list-style-type: none"> • Concrete (miscellaneous): Always sample as near as practicable to the point of placement. For strength testing, vary the time of day or the number of truck from which the concrete is sampled.
C	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE V – HYDRAULIC CEMENT CONCRETE PAVEMENT (Classes: P or HES)

			PROJECT TESTS			
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING	FREQUENCY OF SAMPLING (D)	REMARKS	
MINERAL AGGREGATE	COARSE AGGREGATE	Decantation	Tex-406-A	From stockpile at concrete plant	Each 20,000 CY of concrete (each source)	Sample in accordance with Tex-400-A.
		Sieve Analysis (A)	Tex-401-A		As necessary for control	Sample in accordance with Tex-400-A. Test combined aggregate when used.
		Deleterious Materials	Tex-413-A		Each 20,000 CY of concrete (each source)	Sample in accordance with Tex-400-A.
		L.A. Abrasion (A)	Tex-410-A		One, each source	Verify the value of the source, as listed on the current CRSQC, meets the project specifications. If not, sample and submit to MTD for testing before use in accordance with Tex-499-A. Sample in accordance with Tex-400-A. (C)
		Magnesium Soundness (A)	Tex-411-A			
	FINE AGGREGATE	Sand Equivalent	Tex-203-F	From stockpile at concrete plant	Each 3,000 CY of concrete (Each source or combination of sources)	Sample in accordance with Tex-400-A. Test combined aggregate when used. At least one per week's production.
		Organic Impurities	Tex-408-A		1 per project, per source	Sample in accordance with Tex-400-A.
		Sieve Analysis (A)	Tex-401-A		As necessary for control	Sample in accordance with Tex-400-A. Test combined aggregate when used.
		Fineness Modulus (B)	Tex-402-A			
		Deleterious Material (B)	Tex-413-A		Each 20,000 CY of concrete (each source)	Sample in accordance with Tex-400-A.
		Acid Insoluble (A)	Tex-612-J		1 per project, per source	Verify the value of the source, as listed on the current CRSQC, meets the project specifications. If not, sample and submit to MTD for testing before use in accordance with Tex-499-A. Sample in accordance with Tex-400-A. (C)
MIX DESIGN	Compliance with the Standard Specifications Item 421.4.A		At source, if not approved	Min. 1 design, per class, per source	Verify if cement, fly ash, ground granulated blast furnace slag, and admixture sources are listed on the Material Producer List. If not, sample and submit to MTD for testing. Sample in accordance with Tex-300-D for cement and in accordance with Tex-733-I for fly ash. Water testing is contracted by the concrete supplier (commercial lab report to be reviewed by TxDOT).	
SILICA FUME	Compliance with DMS-4630		Railroad car, truck, bags, or silos	1 per project, per class of concrete (For each type and brand)	Sample in accordance with Tex-300-D. Provide MTD with one 4 x 8 concrete sample for silica fume dispersion verification. Verify the source is listed on the Material Producer List for Silica Fume.	

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE V – HYDRAULIC CEMENT CONCRETE PAVEMENT (Classes: P or HES)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING	FREQUENCY OF SAMPLING (D)	REMARKS
METAKAOLIN	Compliance with DMS-4635		Railroad car, truck, or silos	1 per project, per class of concrete (For each type and brand)	Sample in accordance with Tex-300-D.
JOINT MATERIAL	Compliance with DMS-6310		Sampled at jobsite if not sampled at source by MTD ; tested by MTD . See remarks.	1 per batch or shipment	Sample in accordance with Tex-500-C. Sampling may be waived when the source is listed on the Material Producer List for Joint Sealers . (C)
CURING COMPOUND	Compliance with DMS-4650		Sampled at jobsite; tested by MTD . See remarks.	When requested by MTD	Only products listed on the Material Producer List for Concrete Curing Compounds will be allowed. When sample is requested by MTD , sample in accordance with Tex-718-I. Ensure container has been agitated and mixed before sampling. (C)
EVAPORATION RETARDANTS	Compliance with DMS-4650				Only products listed on the Material Producer List for Evaporation Retardants will be allowed. (C)
REINFORCING STEEL	Compliance with the Std. Specifications & Spec. Provisions	As Specified			Only materials from MTD approved sources listed on the Material Producer List for Reinforcing Steel Mills and Seven Wire Steel Strand will be accepted. (C)
MULTIPLE PIECE TIE BARS	Compliance with DMS-4515	Tex-712-I	Sampled at jobsite if not sampled at source by MTD ; tested by MTD . See remarks.	Refer to Tex-711-I for sampling rates	Only materials from MTD approved sources listed on the Material Producer List for Multiple Piece Tie-bars for Concrete Pavements will be allowed. Sample in accordance with Tex-711-I.
EPOXY	Compliance with DMS-6100		Sampled at jobsite if not pre-approved by MTD . See remarks.	1 batch per shipment	Verify the source is listed on the Material Producer List for Epoxyes and Adhesives . If not, sample and test before use in accordance with DMS-6100. Sample in accordance with Tex-734-I. (C)
CONCRETE	Strength (A) (B)	Tex-448-A or Tex-418-A	At point of concrete placement	2 cylinders for every 10 contractor job control tests	Sample in accordance with Tex-407-A. When the contract requires the project testing to be by the Engineer, the frequency and job control testing will be in accordance with the item of work. Split sample verification testing used when contractor performs job control testing. When job control testing by the contractor is waived by the plans, the frequency of sampling will be one test (2 specimens) for each 3,000 SY of concrete or fraction thereof or per day and split sample verification testing will be waived. Contractor's required testing will be in accordance with specification requirements for the appropriate specification Item #.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE V – HYDRAULIC CEMENT CONCRETE PAVEMENT (Classes: P or HES)

PROJECT TESTS					
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OR TIME OF SAMPLING	FREQUENCY OF SAMPLING (D)	REMARKS
CONCRETE (Continued)	Slump	Tex-415-A	At time and location strength specimens are made	1 test for every 10 contractor job control tests.	Sample in accordance with Tex-407-A. Slump is not required for slip-formed pavement. Perform slump and temperature tests on the same load from which the strength specimens are made. Perform entrained air test only when entrained air concrete is specified on the plans. Contractor's required testing will be in accordance with specification requirements for the appropriate specification Item #.
	Entrained Air (A)	Tex-416-A or Tex-414-A			
	Temperature	Tex-422-A			
	Pavement Texture	Tex-436-A	Final Riding Surface of travel lanes	1 per day, per driving lane	Perform when carpet drag is the only surface texture required on the plans.
	Thickness	Tex-423-A, Part I	Center of paving machine	Every 500 feet	Methods other than Tex-423-A may be shown on the plans.
	Ride Quality (A)	Tex-1001-S Surface Test, Type B	Final riding surface of travel lanes		Engineer may verify contractor's results for surface test Type B. For traditional design-bid-build TxDOT projects, MTD has contracted with TTI to perform random ride verification at 10% frequency. Results from surface test Type A are not required to be reported.

TABLE V – FOOTNOTES

A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	When a project test does not meet the specified strength requirements and a reduced pay factor is assigned, document the analysis on the Letter of Certification of Materials Used.
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	Each test performed, that is based on a quantity of material, is considered "or fraction thereof" for calculating number of tests.

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VI – HOT-MIX ASPHALT PAVEMENT (Items 341, 342, 344, 346, 347 and 348)
 (All testing as noted in Table VI may be waived for exempt production as defined by specification.)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION (Per Design)	FREQUENCY OF SAMPLING (E)	REMARKS
COARSE AGGREGATE	L. A. Abrasion (A)	Tex-410-A	Stockpile (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer list for BRSQC , meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing before use in accordance with Tex-499-A. (C)
	Magnesium Soundness (A)	Tex-411-A			
	Surface Aggregate Classification (A)	Tex-499-A		1 per project, per source	
	Micro Deval	Tex-461-A		1 per project, per aggregate source	
COMBINED AGGREGATE	Sand Equivalent	Tex-203-F	Stockpiles, hot bins, or feeder belts	1 per project, per source, per design	Does not apply to Item 342. Sample in accordance with Tex-221-F. The timing of when the test is performed is at the discretion of the Engineer.
ASPHALT BINDER	Compliance with Item 300 (A)		Sampling port nearest the storage tank	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample binder at hot- mix plant in accordance with Tex-500-C, Part II. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant. The Engineer must associate one QM sample, per project in SM.
TACK COAT	Compliance with Item 300 (A)		Distributor	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample tack coat in accordance with Tex-500-C, Part III. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant. The Engineer must associate one QM sample, per project in SM.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VI – HOT-MIX ASPHALT PAVEMENT (Items 341, 342, 344, 346, 347 and 348)
(All testing as noted in Table VI may be waived for exempt production as defined by specification.)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION (Per Design)	FREQUENCY OF SAMPLING (E)	REMARKS
MIX DESIGN	Compliance with applicable specification	Tex-204-F	At source (if not approved)	Min 1 design, per Mix Type and Asphalt Grade	Verify that aggregates, recycled asphalt pavement, recycled asphalt shingles, mineral filler, asphalt binder, anti-stripping additives, and warm mix systems are on the Material Producer List where applicable and that they meet project specification requirements. Project sampling and testing may be conducted on individual materials, as necessary, for control.
COMPLETE MIXTURE	Asphalt Content (A)	Tex-236-F	Engineer Truck Sample (D)	Minimum 1 per Lot	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project. When Tex-236-F does not yield reliable results, use alternative methods for determining asphalt content, such as, Tex-210-F (ASTM D2172/AASHTO T164) and Tex-228-F (ASTM D4125/AASHTO T287).
	Voids in Mineral Aggregates (VMA)	Tex-204-F	Truck Sample Plant Produced (D)	1 per Sublot	Sample in accordance with Tex-222-F. Contractor's required testing will be in accordance with specification requirements for the appropriate specification Item #. Does not apply to Items 342 and 348.
	Gradation (A)	Tex-200-F	Engineer Truck Sample (D)	Minimum 1, per 12 Sublots (E)	Sample in accordance with Tex-222-F. Determine correction factors for ignition oven using Tex-236-F at a minimum of one per project.
	Moisture Susceptibility	Tex-530-C	Truck Sample	1 per project	Sample in accordance with Tex-222-F, unless waived by the Engineer.
	Indirect Tensile Strength – Dry	Tex-226-F			Sample in accordance with Tex-222-F, unless waived by the Engineer. Does not apply to Items 342, 346, 347, and 348.
	Moisture Content	Tex-212-F, Part II	Engineer Truck Sample		Sample in accordance with Tex-222-F.
	Lab Molded Density (A)	Tex-207-F, Part I, VI, VIII	Truck Sample (D)	1 per Sublot 1 per Lot for Item 347	Sample in accordance with Tex-222-F. Contractor's required testing will be in accordance with specification requirements for the appropriate specification Item #.
	Drain Down Test (A)	Tex-235-F	Engineer Truck Sample	1 per 12 Sublots	Sample in accordance with Tex-222-F. Not required for Items 341, 344, and 347.
	Hamburg Wheel Test (A)	Tex-242-F	Engineer Truck Sample	1 per project	Sample in accordance with Tex-222-F. Sample during production. Does not apply to Item 348 PFC-C, PFCR-C, and Thin Bonded Wearing Course –All Types.

This is a guide for **minimum sampling and testing**.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VI – HOT-MIX ASPHALT PAVEMENT (Items 341, 342, 344, 346, 347 and 348)
 (All testing as noted in Table VI may be waived for exempt production as defined by specification.)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION (Per Design)	FREQUENCY OF SAMPLING (E)	REMARKS
COMPLETE MIXTURE (Continued)	Cantabro Loss (A)	Tex-245-F	Engineer Truck Sample	1 per project	Sample in accordance with Tex-222-F. Sample during production. Does not apply to items 341, 344, 346, and 347.
	Overlay Test (A)	Tex-248-F	Engineer Truck Sample	1 per project	Sample in accordance with Tex-222-F. Does not apply to Items 341, 344, and 348 PFC-C, PFCR-C, and Thin Bonded Wearing Course –All Types.
ROADWAY	In-Place Air Voids (A)	Tex-207-F, Part I, VI, VIII	Roadway (D)	2 cores per Sublot	Two cores taken per Sublot and averaged. Sample in accordance with Tex-222-F. Does not apply to Items 342, 347, and 348.
	Segregation Profile (A)	Tex-207-F, Part V	Roadway	1 per project	Not required when Contractor uses thermal imaging system. Does not apply to Items 342, 347, and 348.
	Joint Density (A)	Tex-207-F, Part VII	Roadway	1 per project	
	Thermal Profile	Tex-244-F	Immediately behind paver	1 per project	Not required when Contractor uses thermal imaging system.
	Ride Quality Test Type B (A)	Tex-1001-S	Final riding surface of travel lanes	1 per project	Engineer may verify Contractor's results for surface test Type B. For traditional design-bid-build TxDOT projects, MTD has contracted with TTI to perform random ride verification at 10% frequency. Results for surface test Type A are not required to be reported.
	Permeability	Tex-246-F	Roadway	1 per project	Permeability is encouraged to use with items 342 and 348. Only applies to Item 347.
FABRIC UNDERSEAL	Compliance with DMS-6220		Sampled, tested, and approved by MTD		Sampling must be in accordance with Tex-735-I. Verify the source is listed on the current Material Producer List for Silt Fence, Filter Fabric, and Fabric Underseals . If not, sample and test before use in accordance with DMS-6220.

TABLE VI – FOOTNOTES

A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	Sampling may be performed at the plant, quarry, or both. Aggregate properties may be re-tested at any time during the project. These project tests may be used for one or more projects furnishing hot mix with the same aggregate source.
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	Perform random sampling as specified in Tex-225-F, "Random Selection of Bituminous Mixture Samples."
E	Each test performed, that is based on a quantity of material, is considered "or fraction thereof" for calculating number of tests.

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VII – HOT-MIX ASPHALT PAVEMENT (Items 334) (Refer to DMS-9210, “Limestone Rock Asphalt (LRA),” for testing requirements for Item 330.)					
			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION	FREQUENCY (Per Design) (F)	REMARKS
COARSE AGGREGATE	L. A. Abrasion (A)	Tex-410-A	Stockpile (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing before use in accordance with Tex-499-A. (D) Sample in accordance with Tex-221-F. Testing frequency may be reduced or eliminated based on a satisfactory test history.
	Magnesium Soundness (A)	Tex-411-A			
	Micro Deval	Tex-461-A			
	Surface Aggregate Classification (A)	Tex-499-A	Stockpile (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing before use in accordance with Tex-499-A. SiteManager Quality Monitoring test documentation is accomplished by attaching an approved mix design.
COMBINED AGGREGATE	Sand Equivalent	Tex-203-F	Stockpiles, hot bins, or feeder belts	1 per project, per source	Sample in accordance with Tex-221-F. The timing of when the test is performed is at the discretion of the Engineer.
ASPHALT BINDER	Compliance with Item 300 (A)		Sampling port nearest the storage tank	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample binder in accordance with Tex-500-C, Part II. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant. The Engineer must associate one QM sample, per project in SM.
TACK COAT	Compliance with Item 300 (A) (C)		Distributor	1 per project, per grade, per source	Test a minimum of one sample taken from the project. Sample tack coat in accordance with Tex-500-C, Part III. Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant. The Engineer must associate one QM sample, per project in SM.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VII – HOT-MIX ASPHALT PAVEMENT (Items 334)

(Refer to DMS-9210, “Limestone Rock Asphalt (LRA),” for testing requirements for Item 330.)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION	FREQUENCY (Per Design) (F)	REMARKS
MIX DESIGN	Compliance with applicable specification	Tex-204-F	At source (if not approved)	Min 1 design per Mix Type and Asphalt Grade	Verify that aggregates, recycled asphalt pavement, recycled asphalt shingles, mineral filler, asphalt binder, anti-stripping additives, and warm mix systems are on the Material Producer List where applicable and that they meet project specification requirements. Project sampling and testing may be conducted in individual materials as necessary for control.
COMPLETE MIXTURE	Asphalt Content (A)	Tex-236-F	Engineer Truck Sample (E)	Minimum of 1 per 5,000 tons	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project.
	Voids in Mineral Aggregates (VMA)	Tex-204-F	Truck Sample Plant Produced (E)	1 per 5,000 tons	Sample in accordance with Tex-222-F.
	Gradation (A)	Tex-236-F	Truck Sample	Minimum 1 per 5,000 tons	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project.
	Boil Test	Tex-530-C		1 per project	Sample in accordance with Tex-222-F. The timing of when the test is performed is at the discretion of the Engineer.
	Moisture Content	Tex-212-F, Part II	Truck Sample	1 per 5,000 tons	Sample in accordance with Tex-222-F. Performed by MTD at the point of production for payment calculations.
	Hydrocarbon-Volatile Content	Tex-213-F		1 per 5,000 tons	Sample in accordance with Tex-222-F. The timing of when the test is performed is at the discretion of the Engineer.
	Lab Molded Density (A)	Tex-207-F		1 per 5,000 tons	Sample in accordance with Tex-222-F.
Hveem Stability (A)	Tex-208-F	1 per 5,000 tons		Sample in accordance with Tex-222-F. The timing of when the test is performed is at the discretion of the Engineer.	
ROADWAY	Ride Quality Test Type B (A)	Tex-1001-S	Final riding surface of travel lanes		Engineer may verify Contractor’s results for surface test Type B. For traditional design-bid-build TxDOT projects, MTD has contracted with TTI to perform random ride verification at 10% frequency. Results from surface test Type A are not required to be reported.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VII – FOOTNOTES

A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	Sampling may be performed at the plant, quarry, or both. Aggregate properties may be re-tested at any time during the project.
C	Or as called for in the Specifications.
D	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
E	Perform random sampling as specified in Tex-225-F, “Random Selection of Bituminous Mixture Samples.”
F	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VIII – HOT-MIX ASPHALT PAVEMENT (Item 340)

			PROJECT TESTS			
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION	FREQUENCY	REMARKS	
COARSE AGGREGATE	L. A. Abrasion (A)	Tex-410-A	Stockpile (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer List for BRSQC , meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing before use in accordance with Tex-499-A. (C)	
	Magnesium Soundness (A)	Tex-411-A				
	Micro Deval	Tex-461-A	Stockpile (B)	1 per project, per source		Sample in accordance with Tex-221-F. Testing frequency may be reduced or eliminated based on a satisfactory test history.
	Surface Aggregate Classification (A)	Tex-499-A	Stockpile (B)	1 per project, per source		Verify the published value of the source, as listed on the current Material Producer list for BRSQC , meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing before use in accordance with Tex-499-A. (C)
COMBINED AGGREGATE	Sand Equivalent	Tex-203-F	Stockpiles, hot bins, or feeder belts	1 per project, per design	Sample in accordance with Tex-221-F.	
ASPHALT BINDER	Compliance with Item 300 (A)		Sampling port nearest the storage tank	1 per project, per grade, per source	<p>Test a minimum of one sample taken from the project. Sample binder in accordance with Tex-500-C, Part II.</p> <p>Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant.</p> <p>The Engineer must associate one QM sample, per project in SM.</p>	
TACK COAT	Compliance with Item 300 (A)		Distributor	1 per project, per grade, per source	<p>Test a minimum of one sample taken from the project. Sample tack coat in accordance with Tex-500-C, Part III.</p> <p>Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant.</p> <p>The Engineer must associate one QM sample, per project in SM.</p>	
MIX DESIGN	Compliance with applicable specification	Tex-204-F	At source (if not approved)	Min. 1 design per Mix Type and Asphalt Grade	Verify that aggregates, recycled asphalt pavement, recycled asphalt shingles, mineral filler, asphalt binder, anti-stripping additives, and warm mix systems are on the Material Producer List where applicable and that they meet project specification requirements. Project sampling and testing may be conducted in individual materials as necessary for control.	

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VIII – HOT-MIX ASPHALT PAVEMENT (Item 340)

			PROJECT TESTS		
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION	FREQUENCY	REMARKS
COMPLETE MIXTURE	Asphalt Content	Tex-236-F	Truck Sample (D)	Minimum of 1 per day	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project.
	Voids in Mineral Aggregates (VMA)	Tex-204-F	Truck Sample Plant Produced (D)	1 per day	Sample in accordance with Tex-222-F.
	Gradation (A)	Tex-236-F	Truck Sample	Minimum 1 per day	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project.
	Boil Test	Tex-530-C		1 per project	Sample in accordance with Tex-222-F, unless waived by the Engineer.
	Indirect Tensile Strength – Dry	Tex-226-F		1 per project, per design	Sample in accordance with Tex-222-F, unless waived by the Engineer.
	Lab Molded Density (A)	Tex-207-F	Truck Sample	1 per day	Sample in accordance with Tex-222-F.
	Hamburg Wheel Tracker (A)	Tex-242-F		1 per project	Sample in accordance with Tex-222-F. Sample during production.
ROADWAY	Air Voids (A)	Tex-207-F	Selected by the Engineer (D)	1 per day (2 Cores)	Sample in accordance with Tex-222-F.
	Ride Quality Test Type B (A)	Tex-1001-S	Final riding surface of travel lanes		Engineer may verify Contractor's results for surface test Type B. For traditional design-bid-build TxDOT projects, MTD has contracted with TTI to perform random ride verification at 10% frequency. Results from surface test Type A are not required to be reported.
FABRIC UNDERSEAL	Compliance with DMS-6220		Sampled, tested, and approved by MTD		Sample in accordance with Tex-735-I. Verify the source is listed on the current Material Producer List for Silt Fence, Filter Fabric, and Fabric Underseals. If not, sample and submit to MTD for testing before use in accordance with DMS-6220.

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE VIII – FOOTNOTES

A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	Sampling may be performed at the plant, quarry, or both. Aggregate properties may be re-tested at any time during the project. These project tests may be used for one or more projects furnishing hot mix with the same aggregate source.
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	Perform random sampling as specified in Tex-225-F, “Random Selection of Bituminous Mixture Samples.”

This is a guide for minimum sampling and testing.
Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IX – MICROSURFACING (Item 350)

PROJECT TESTS					
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OF SAMPLING	FREQUENCY (Per Design)	REMARKS
AGGREGATE	Magnesium Soundness (A)	Tex-411-A	Stockpile (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer list for BRSQC meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing at 1 per project, per source. (C)
	Gradation	Tex-200-F, Part II		1 per project, per source	Sample in accordance with Tex-221-F.
	Crushed Face Count	Tex-460-A		1 per project, per source	Sample in accordance with Tex-221-F.
	Acid Insoluble (A)	Tex-612-J		1 per project, per source	Verify the value of the source, as listed on the current BRSQC, meets the project specifications. If not, sample and submit to MTD for testing before use in accordance with Tex-499-A. Sample in accordance with Tex-221-F. (C)
	Surface Aggregate Classification	Tex-499-A	Stockpile, or BRSQC (B)	1 per project, per source	Verify the published value of the source, as listed on the current Material Producer list for BRSQC meets the project specifications. If not, sample in accordance with Tex-221-F and submit to MTD for testing at 1 per project, per source. (C)
COMBINED BLEND	Sand Equivalent	Tex-203-F	Stockpile (B)	1 per project, per source	Sample in accordance with Tex-221-F.
ASPHALT BINDER	Compliance with Item 300 (A)		Sampling port nearest the storage tank	1 per project, per grade, per source	<p>Test a minimum of one sample taken from the project. Sample binder in accordance with Tex-500-C, Part II.</p> <p>Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant.</p> <p>The Engineer must associate one QM sample, per project in SM.</p>
TACK COAT	Compliance with Item 300 (A)		Distributor	1 per project, per grade, per source	<p>Test a minimum of one sample taken from the project. Sample tack coat in accordance with Tex-500-C, Part III.</p> <p>Verify that the binder is from a preapproved source when it arrives on the project, and that the lab number on the shipping ticket is within the valid dates shown on the MTD QM test report or in the SM Assistant.</p> <p>The Engineer must associate one QM sample, per project in SM.</p>

This is a guide for minimum sampling and testing.
 Testing frequency may need to be increased for high material variability or when test results approach specification limits.

TABLE IX – MICROSURFACING (Item 350)

PROJECT TESTS					
MATERIAL OR PRODUCT	TEST FOR	TEST NUMBER	LOCATION OF SAMPLING	FREQUENCY (Per Design)	REMARKS
MIX DESIGN	Compliance with applicable specification	Tex-204-F	At source (if not approved)	Min. 1 design per project	Submit to MTD for approval.
CEMENT	Compliance with DMS-4600				Verify the source is listed on the current Material Producer List for Cement . If not, sample and submit to MTD for testing before use in accordance with DMS-4600.
COMPLETE MIX	Asphalt Content	Tex-236-F	During production	1 per day	Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven using Tex-236-F at a minimum of one per project.
	Gradation	Tex-200-F, Part II Tex-236-F			Sample in accordance with Tex-222-F. Determine correlation factors for ignition oven use at a minimum of one per project.

TABLE IX – FOOTNOTES

A	When this project acceptance test fails, but the product is accepted, document the reasons for acceptance in SiteManager, in the remarks field, and on the end of the Project Materials Certification Letter.
B	Sampling may be performed at the plant, quarry, or both. Aggregate properties may be re-tested at any time during the project. These project tests may be used for one or more projects furnishing hot mix with the same aggregate source.
C	Attach the corresponding QM test report for SiteManager projects to satisfy project sampling and testing requirements.
D	Each test performed, that is based on a quantity of material, is considered “or fraction thereof” for calculating number of tests.

PART C

BID QUANTITIES

Construction of South County Road 1232 Driveway at State Highway 158

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Base Bid					
Item	Description				
1	Preparing ROW	1	STA		
2	Traffic Control	4	MO		
3	SWPPP ≥ 1 acre	4	MO		
4	Excavation	92	CY		
5	Embankment	179	CY		
6	Prime Coat (MC-30)	453	GAL		
7	Tack Coat (RC-250)	227	GAL		
8	D-GR HMA(SQ) TY-B PG64-22	133	TN		
9	D-GR HMA(SQ) TY-D PG70-22	2,128	TN		
10	FL BS (CMP IN PLC)(TY A GR 4) (8")	25,218	SY		
11	FL BS (CMP IN PLC)(TY A OR B GR 4) (18")	645	SY		
12	Furnish and Install Small Sign Assembly	5	EA		
13	REFL PAV MRKR TY 1-C	68	EA		
14	REFL PAV MRKR TY II-A-A	544	EA		
15	REFL PAV MRK TY II (W) 4" (BRK)	5,260	LF		
16	REFL PAV MRK TY II (W) 4" (SLD)	5,818	LF		
17	REFL PAV MRK TY II (W) 8" (SLD)	1,050	LF		
18	REFL PAV MRK TY II (W) 18" (SLD)	24	LF		
19	REFL PAV MRK TY II (Y) 4" (SLD)	8,900	LF		
20	REFL PAV MRK TY II (Y) 8" (SLD)	86	LF		

Construction of South County Road 1232 Driveway at State Highway 158

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Base Bid					
Item	Description				
21	Protect Sewer Manhole	1	EA		
22	CONC BOX CULV (5 FT X 2 FT)	114	LF		
23	RC PIPE (CL III)(18 IN)	25	LF		
24	WINGWALL (FW - S) (HW=5 FT) w/6:1 SET	2	EA		
25	SET (TY II) (18 IN) (RCP) (6: 1) (C)	2	EA		
26	REMOV STR (HEADWALL)	2	EA		
27	Mobilization	1	LS		
TOTAL BASE BID					
CONSTRUCTION START DATE					
TOTAL CALENDAR DAYS					