

Construction of South County Road 1232 Driveway at State Highway 158

Roadway Improvements to Serve Midland County					
		Quantity	Unit	Unit Price	Total
Base Bid - Revised 11/16/21					
Item	Description				
1	PREPARING ROW	1	STA		
2	TRAFFIC CONTROL	4	MO		
3	SWPPP ≥ 1 acre	4	MO		
4	EXCAVATION	92	CY		
5	EMBANKMENT	179	CY		
6	PRIME COAT (AE-P)	1,048	GAL		
7	TACK COAT	2,522	GAL		
8	D-GR HMA TY-B PG64-22 (EXEMPT)	1,001	TN		
9	D-GR HMA TY-D PG64-22 (EXEMPT)	2,287	TN		
10	FL BS (CMP IN PLC)(TY A GR 4) (8")	4,352	SY		
11	FL BS (CMP IN PLC)(TY A GR 4) (18")	645	SY		
12	FURNISH AND INSTALL SMALL SIGN ASSEMBLY	5	EA		
13	REFL PAV MRKR TY 1-C	68	EA		
14	REFL PAV MRKR TY II-A-A	544	EA		
15	REFL PAV MRK TY II (W) 4" (BRK)	5,260	LF		
16	REFL PAV MRK TY II (W) 4" (SLD)	5,818	LF		
17	REFL PAV MRK TY II (W) 8" (SLD)	1,050	LF		
18	REFL PAV MRK TY II (W) 18" (SLD)	24	LF		
19	REFL PAV MRK TY II (Y) 4" (SLD)	8,900	LF		
20	REFL PAV MRK TY II (Y) 8" (SLD)	86	LF		

Construction of South County Road 1232 Driveway at State Highway 158

Roadway Improvements to Serve Midland County		Quantity	Unit	Unit Price	Total
Base Bid - Revised 11/16/21					
Item	Description				
21	PROTECT SEWER MANHOLE	1	EA		
22	CONC BOX CULV (5 FT X 2 FT)	114	LF		
23	RC PIPE (CL III)(18 IN)	25	LF		
24	WINGWALL (FW - S) (HW=5 FT) w/6:1 SET	2	EA		
25	SET (TY II) (18 IN) (RCP) (6: 1) (C)	2	EA		
26	REMOV STR (HEADWALL)	2	EA		
27	REMOVE AND RELOCATE EXISTING ATTENUATOR	2	EA		
28	RIPRAP (STONE PROTECTION)(12 IN)	10.7	CY		
29	BEDDING MATERIAL (3 IN)	2.7	CY		
30	MOBILIZATION	1	LS		
TOTAL BASE BID					
CONSTRUCTION START DATE					
TOTAL CALENDAR DAYS					