

## Reconstruction of SCR 1180

| Roadway Improvements to Serve Midland County |  | Quantity | Unit | Unit Price | Total |
|--|--|----------|------|------------|-------|
| <b>Base Bid - Revised 04/08/2022</b>         |  |          |      |            |       |
| Item   | Description  |          |      |            |       |
| 1  | Preparation of R.O.W.                                | 47       | Sta. |            |       |
| 2  | Sawcut Existing Asphalt (full depth)                 | 62       | L.F. |            |       |
| 3  | Asphalt Excavation - 1.25 inch depth (average)       | 536      | C.Y. |            |       |
| 4  | Asphalt Haul Off                                     | 536      | C.Y. |            |       |
| 5  | Earthwork*   | 8,508    | C.Y. |            |       |
| 6  | Haul Off   | 8,509    | C.Y. |            |       |
| 7  | Subgrade Preparation                                 | 18,723   | S.Y. |            |       |
| 8  | Prime Coat**   | 4,993    | Gal. |            |       |
| 9  | Flexible Base (Roadway)                              | 6,473    | C.Y. |            |       |
| 10   | HMA Pavement - 5" thickness - Type D**               | 4,785    | Ton  |            |       |
| 11   | 6" Concrete Commercial Driveways                     | 330      | S.Y. |            |       |
| 12   | 3" HMA on 8" Base Commercial Driveway                | 220      | S.Y. |            |       |
| 13   | 8" Compacted Base Commercial Driveway                | 1,560    | S.Y. |            |       |
| 14   | 6" Concrete Residential Driveways                    | 30       | S.Y. |            |       |
| 15   | 8" Compacted Base Residential Driveway               | 60       | S.Y. |            |       |
| 16   | 60'X5' Pipeline Cap                                  | 1        | Ea.  |            |       |
| 17   | Reflective Marking (Type 1) 4" Double Yellow Striped | 5        | Sta. |            |       |
| 18   | Reflective Marking (Type 1) 4" Broken Yellow Striped | 43       | Sta. |            |       |
| 19   | Reflective Marking (Type 1) 4" White Striped         | 45       | Sta. |            |       |
| 20   | Surface Preparation for Pavement Marking             | 45       | Sta. |            |       |
| 21   | IN SM RD SN SUP&AM TY10BWG(1) SA (P)                 | 8        | Ea.  |            |       |
| 22   | Aluminum Signs                                       | 49       | S.F. |            |       |

## Reconstruction of SCR 1180

| Roadway Improvements to Serve Midland County |                     | Quantity | Unit | Unit Price | Total |
|--|---------------------|----------|------|------------|-------|
| <b>Base Bid - Revised 04/08/2022</b>         |                     |          |      |            |       |
| Item   | Description         |          |      |            |       |
| 23   | Mailbox Relocations | 1        | Ea.  |            |       |
| 24   | Erosion Control     | 1        | L.S. |            |       |
| 25   | Traffic Control     | 1        | L.S. |            |       |
| 26   | Mobilization        | 1        | LS   |            |       |
| <b>TOTAL BASE BID</b>                        |                     |          |      |            |       |
| <b>CONSTRUCTION START DATE</b>               |                     |          |      |            |       |
| <b>TOTAL CALENDAR DAYS</b>                   |                     |          |      |            |       |

Contractor shall notify the Engineer of Record of any discrepancies in quantities prior to the commencement of construction.

\* Quantities do not include factors for compaction and expansion.

\*\* Rates used for calculation purposes only:

Prime Coat: 0.3 Gal/SY

HMA Pavement - 3" thickness - Type D: 115 lb/SY\*in