



Request for Proposal, 22MCO596
In response refer to RFP No. 22MCO596 Response to Additional Questions
September 14, 2021

Gentlemen/Ladies:

This document contains questions submitted by prospective bidders and responses to those questions.

1. The alternate that removes the cast in place box culvert from the base bid and adds precast box culverts has a couple of errors. There should be a negative bid item that removes the headwalls from the base bid (just like the CIP Box Culvert was removed). The headwalls for the precast option will be longer and therefore a different price for the 2 EA. Also the quantity of -21 LF for the wingwalls should be -42 LF (the -21 LF covers only one side).

The headwalls are an each quantity, and as such, we have 2 each regardless of base bid to alternate bid. The intent on the alternate bid is for the contractor to place the difference in unit cost based on the difference between a precast to cast-in-place box culverts. If the precast box alternative is used, the final cost of the headwall will be the sum of the price in the base bid plus the additional cost included in the alternate bid (Base Bid Item 26 + A25 = total cost to construct headwall if precast boxes are used).

The quantity for the change in wingwalls is correct. The headwall length only changes ~10.5' on each side between the cast-in-place and precast box options. The overall length of the headwall plus the wingwalls remains the same, regardless of the type of box culverts used.