



**RFP 24MCO630**

**In response refer to RFP No. 24MCO630 Addendum 2**

**May 14, 2024**

Gentlemen/Ladies:

This addendum is being issued to include the bid response document, see pages 2 and 3 of this addendum.

**MUNICIPAL WATER AND SANITARY SEWER IMPROVEMENTS PROPOSAL**  
**for**  
**SE Regional Water Line**  
**April 12, 2024**

The undersigned Bidder proposes to complete all the work and furnish all necessary materials, equipment, tools, labor, on-site superintendence, and anything else necessary to complete the work in accordance with the approved construction documents and as provided by standard City of Midland specifications within the time stated and for the following prices. This is a "unit price" proposal. The Contractor shall be paid based on the actual measured quantities installed at the following prices.

ITEM NO.	QUANTITY	DESCRIPTION	UNIT PRICE	TOTAL PRICE
W-1	925 LF	12" C-900, DR-18 PVC water pipe, including all necessary accessories, furnished and installed, complete and in place, per linear foot:	Dollars \$ _____ = \$ _____	
W-2	3,170 LF	8" C-900, DR-18 PVC water pipe, including all necessary accessories, furnished and installed, complete and in place, per linear foot:	Dollars \$ _____ = \$ _____	
W-3	10 LF	6" C-900, DR-18 PVC water pipe, including all necessary accessories, furnished and installed, complete and in place, per linear foot:	Dollars \$ _____ = \$ _____	
W-4	3 Ea	12" Valve with Valve Box Assembly and Cover, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-5	7 Ea	8" Valve with Valve Box Assembly and Cover, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-6	1 Ea	6" Valve with Valve Box Assembly and Cover, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-7	1 Ea	12" Tapping Sleeve and Valve, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-8	1 Ea	6"x12" Tapping Sleeve and Valve, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-9	1 Ea	12"x8" Tee, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-10	2 Ea	8"x8" Tee, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-11	2 Ea	12" 45 Degree Bend, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-12	4 Ea	12" 45 Degree Vertical Bend, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-13	3 Ea	8" water line Cap, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	
W-14	1 Ea	6" water line Cap, including joint restraints and all necessary accessories, furnished and installed, complete and in place, per each:	Dollars \$ _____ = \$ _____	

W-15	100 LF	24" Steel Pipe Casing, including all necessary accessories, furnished and installed, complete and in place, per linear foot:				
				Dollars	\$	= \$
W-16	1 Ea	Tie in to water line stub out , accessories, excavation and backfill, furnished and installed, complete and in place, per each:				
				Dollars	\$	= \$
W-17	1 Ea	Water line tap for future City meter , accessories, excavation and backfill, furnished and installed, complete and in place, per each:				
<b>TOTAL FOR WATER</b>						<b>\$</b>

**THE FOLLOWING ARE THE SUBTOTALS COMPRISING THE TOTAL BID LISTED ABOVE:**

Materials physically incorporated into the work constructed:	\$
All necessary materials, labor, equipment, tools, insurance, bonds, profits and losses, and any other item deemed necessary to complete the work constructed:	\$
<b>TOTAL</b>	<b>\$</b>

**SPECIAL CONDITIONS**

The Contractor shall not begin installation of water service laterals until all other utilities (including electric, gas, cable, and telephone) have been installed in the vicinity of the laterals to be installed. Due to the time expected for utility installation, the Contractor may temporarily demobilize from the project site, provided all other work has been completed and proper site clean-up has been performed. The Contractor agrees to return to the project site within ten (10) calendar days of written request by the Owner to commence the water service lateral installations. The Owner shall be responsible for ensuring that all other utilities have been properly installed prior to written request for water service laterals to be installed.

**DECLARATION OF BIDDER**

The undersigned Bidder hereby declares that he has visited the proposed construction site and has fully examined

\_\_\_\_\_  
CONTRACTOR

\_\_\_\_\_  
SIGNATURE

\_\_\_\_\_  
ADDRESS