

**Occidental Parkway from Carriage Road to Elkins Road
PRICING SHEET**

ITEM NO	SPEC	SPEC NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	BID
SECTION I - PAVING & GENERAL							
1	COM	PREP ROW	PREPARING ROW	STA	90	\$ _____	\$ _____
2	COM	SUBGRADE	EXCAVATION	CY	23,190	\$ _____	\$ _____
3	COM	SUBGRADE	EMBANKMENT	CY	10,147	\$ _____	\$ _____
4	COM	PREP ROW	REMOVING STAB BASE AND ASPH PAVE (12"-18")	SY	45	\$ _____	\$ _____
5	COM	PREP ROW	REMOVING TREATED BASE (8")	SY	12,074	\$ _____	\$ _____
6	COM	CALICHE	12-INCH THICK CALICHE FLEXIBLE BASE	SY	29,237	\$ _____	\$ _____
7	COM	CALICHE	8-INCH THICK CALICHE FLEXIBLE BASE	SY	5,255	\$ _____	\$ _____
8	COM	SUBGRADE	8-INCH PREPARED SUBGRADE	SY	34,492	\$ _____	\$ _____
9	COM	BITUMINOUS PRIME	PRIME COAT (MC-30)	GAL	5,570	\$ _____	\$ _____
10	COM	HMAC	TYPE C HMAC	TON	4,551	\$ _____	\$ _____
11	315	XXXX	FOG SEAL	GAL	3,342	\$ _____	\$ _____
12	360	XXXX	6-INCH FIBER REINFORCED CONCRETE PAVEMENT	SY	514	\$ _____	\$ _____
13	360	XXXX	CONCRETE HEADER	LF	406	\$ _____	\$ _____
14	432	6045	RIPRAP (MOW STRIP) (4 IN)	CY	41	\$ _____	\$ _____

15	496	6001	REMOVE STR (SMALL FENCE)	LF	1,608	\$ _____	\$ _____
16	500	6001	MOBILIZATION	LS	1	\$ _____	\$ _____
17	502	6001	BARRICADES, SIGNS AND TRAFFIC HANDLING	LS	1	\$ _____	\$ _____
18	506	XXXX	STORM WATER POLLUTION PREVENTION PLAN	LS	1	\$ _____	\$ _____
19	506	6002	ROCK FILTER DAMS (INSTALL)(TY 2)	LF	115	\$ _____	\$ _____
20	506	6011	ROCK FILTER DAMS (REMOVE)	LF	115	\$ _____	\$ _____
21	506	6040	BIODEG EROSN CONT LOG (INSTALL) (8")	LF	729	\$ _____	\$ _____
22	506	6043	BIODEG EROSN CONT LOG (REMOVE)	LF	729	\$ _____	\$ _____
23	506	6002	TEMP SEDMT CONT FENCE (INSTALL)	LF	6,299	\$ _____	\$ _____
24	506	6011	TEMP SEDMT CONT FENCE (REMOVE)	LF	6,299	\$ _____	\$ _____
25	COM	CONCRETE 6	CONC CURB AND GUTTER	LF	3,199	\$ _____	\$ _____
26	540	6001	MTL -W-BEAM GD FEN (TIM POST)	LF	831	\$ _____	\$ _____
27	540	6020	MTL -W-BEAM GD FEN (LOW FILL CULVERT)	LF	75	\$ _____	\$ _____
28	540	6016	DOWNSTREAM ANCHOR TERMINAL SECTION	EA	4	\$ _____	\$ _____
29	540	6033	MTL BM GD FEN (LONG SPAN SYSTEM)	EA	4	\$ _____	\$ _____
30	544	6001	GUARDRAIL END TREATMENT (INSTALL)	EA	4	\$ _____	\$ _____
31	552	6003	INSTALL NEW WIRE FENCE (TY C)	LF	1,587	\$ _____	\$ _____

32	636	6001	ALUMINUM SIGNS (TY A)	SF	40	\$ _____	\$ _____
33	644	6001	IN SM RD SN SUP&AM TY 10BWG(1)SA(P)	EA	8	\$ _____	\$ _____
34	644	6076	REMOVE SM RD SN SUP&AM	EA	1	\$ _____	\$ _____
35	644	XXXX	INSTL OM ASSM (OM-3) (TWT) (WAS)(R)	EA	10	\$ _____	\$ _____
36	666	XXXX	REFL PAV MRK TY I (W) 4" (SLD) (090 MIL)	LF	17,706	\$ _____	\$ _____
37	666	6047	REFL PAV MRK TY I (W) 24" (SLD) (090 MIL)	LF	22	\$ _____	\$ _____
38	666	XXXX	REFL PAV MRK TY I (Y) 4" (SLD) (090 MIL)	LF	17,765	\$ _____	\$ _____
39	672	6009	REFL PAV MRKR TY-II-A-A	EA	444	\$ _____	\$ _____
40	678	6001	PAV SURF PREP FOR MARK (4")	LF	35,471	\$ _____	\$ _____
41	678	6008	PAV SURF PREP FOR MARK (24")	LF	22	\$ _____	\$ _____
42	COM	WATER 8, 22, 23	WATER VALVE ADJUSTMENT TO GRADE	EA	2	\$ _____	\$ _____
43	COM	CONCRETE RIPRAP	CONCRETE CAP PROTECTION	SY	1,781	\$ _____	\$ _____

SUBTOTAL - SECTION I - PAVING & GENERAL							\$ _____
SECTION II - DRAINAGE							
44	COM	CONCRETE 6	CONCRETE FLUME	EA	1	\$ _____	\$ _____
45	432	6031	RIPRAP (STONE PROTECTION)(12 IN)	CY	425	\$ _____	\$ _____
46	462	6006	CONC BOX CULV (5 FT X 2 FT)	LF	362	\$ _____	\$ _____

47	462	XXXX	CONC BOX CULV (6 FT X 2 FT)	LF	480	\$ _____	\$ _____	
48	466	6179	WINGWALL (PW-1) (HW=4 FT)	EA	1	\$ _____	\$ _____	
49	467	6001	SET (PIPE RUNNER ASSEMBLY)	EA	32	\$ _____	\$ _____	
50	467	XXXX	SET (TY I)(S=5 FT)(HW=3 FT)(2:1)(C)	EA	6	\$ _____	\$ _____	
51	467	XXXX	SET (TY I)(S=5 FT)(HW=4 FT)(2:1)(C)	EA	4	\$ _____	\$ _____	
52	467	6171	SET (TY I)(S=5 FT)(HW=3 FT)(3:1)(C)	EA	2	\$ _____	\$ _____	
53	467	6175	SET (TY I)(S=5 FT)(HW=4 FT)(3:1)(C)	EA	1	\$ _____	\$ _____	
54	467	6172	SET (TY I)(S=5 FT)(HW=3 FT)(4:1)(C)	EA	6	\$ _____	\$ _____	
55	467	6177	SET (TY I)(S=5 FT)(HW=4 FT)(4:1)(C)	EA	1	\$ _____	\$ _____	
56	467	XXXX	SET (TY I)(S=6 FT)(HW=3 FT)(2:1)(C)	EA	12	\$ _____	\$ _____	
SUBTOTAL - SECTION II - DRAINAGE							\$ _____	
SECTION III - FRANCHISE UTILITIES								
57	N/A	N/A	ABANDONED GAS LINE REMOVAL 3" (IN ROW)	LF	1,425	\$ _____	\$ _____	
58	N/A	N/A	ABANDONED GAS LINE REMOVAL 4" (IN ROW)	LF	1,065	\$ _____	\$ _____	
SUBTOTAL - SECTION III - FRANCHISE UTILITIES							\$ _____	

Subtotal Section I \$ _____
Subtotal Section II \$ _____
Subtotal Section III \$ _____
Total Bid for Project \$ _____
Total Calendar Days for Project \$ _____